

Addendum No. 2
June 22, 2018

THE VILLAGE OF LAKE IN THE HILLS

VILLAGE HALL COUNTER REHAB
HR GREEN Job No. 171851

The contract documents for the above referenced project are hereby amended as set forth below. The information contained within this Addendum No. 2 shall be treated as if it was originally contained within the contract documents.

1. REVISION – COMPLETION DATE

The completion of the project will now have a substantial completion date of SEPTEMBER 28, 2018. The contractor will have 10 working days to complete the punchlist items. Additional time will be granted to complete the installation of the windows, once the winning contractor provides a delivery date. It is understood that the contractor will make every effort to have the windows installed as close to the completion date of the project as possible.

2. CLARIFICATION – OVERHEAD DOORS

There was a note on plan sheet A10.1 pointing to the overhead doors in the Recreation room 126, which indicates the door is to be removed. As discussed at the pre-bid meeting, these doors are to remain in the soffit. Please disregard the note.

3. CLARIFICATION – WALL HEIGHT/FIRE RATING

The new wall separating the new work area from the existing file storage only needs to have the dry wall extended 6" inches above the drop ceiling. No fire rating is required as the room is sprinkled.

The undersigned agrees to be bound by the modifications made within this Addendum No. 1, and hereby waives any and all claims based upon the additional or modified information contained herein.

Acknowledgement of Addendum No. 2

Date: _____

Company Name: _____

Attest:

Signature: _____

Signature: _____

Name: _____

Name: _____