1ST STREET WATER MAIN REPLACEMENT FROM LIBERTY ST TO CHESTNUT ST WILTON, IOWA

CONTRACTOR'S BID DATE:

Wednesday, June 21, 2023 @ 2:00 P.M.

PLACE FOR CONTRACTORS TO SUBMIT BIDS:

City of Wilton City Hall 104 E. 4th Street Wilton, Iowa 52778

ADDENDUM NO.1

June 13, 2023

TO ALL PLANHOLDERS:

The following changes, clarifications, additions, and/or deletions are hereby made a part of the contract documents for the above-referenced project, as fully and completely as if the same were fully set forth therein. All Bidders submitting a Bid on the above Contract shall carefully read this Addendum and give it consideration in the preparation of their Bid.

This Addendum No. 1 consists of the following:

- Addendum No. 1 (pages ADN1-1 through ADN1-2)
- Section 00400 BID FORM ADDENDUM 1 (4 pages)
- Plan Sheet G001 (1 page)

SPECIFICATIONS:


- 1. REFER TO SECTION 00200 INSTRUCTIONS TO BIDDERS
 - a. CHANGE Bid Item 5 from "Water Service Stub 6" to "Water Service Stub"
 - b. ADD Bid Item 21: 6" Granular Surfacing, Quantity 790 tons.
- 2. REFER TO SECTION 00400 BID FORM
 - a. **REPLACE** the Bid Form with the attached.

PLANS:

- 1. REFER TO SHEET G001
 - **a. REPLACE** with the attached.

All bidders shall acknowledge receipt and acceptance of Addendum No. 1 by signing in the space provided on the Bid Form. Bids submitted without Addendum No. 1 being acknowledged will be considered non-responsive.

HR Green, Inc. Project No. 10110158 1st Street Water Main Replacement From Liberty St to Chestnut St Wilton, Iowa ADDENDUM #1



IAN CORBIN, PE HR GREEN, INC. 8710 EARHART LANE CEDAR RAPIDS, IOWA 52404 PHONE: (319) 841-4000

END OF ADDENDUM #1

SECTION 00400 BID FORM ADDENDUM 1

- BID TO: <u>City of Wilton</u> <u>104 E. 4th Street</u> <u>Wilton, Iowa</u>
- 1. The undersigned Bidder proposes and agrees, if this Bid is accepted, to enter into an Agreement with the Owner in the form included in the Contract Documents to perform the WORK as specified or indicated in said Contract Documents entitled:

1st Street Water Main Replacement From Liberty St to Chestnut St

- 2. Bidder accepts all of the terms and conditions of the Contract Documents, including without limitation those in the Notice to Bidders and Instructions to Bidders, dealing with the disposition of the Bid Security.
- 3. Schedule of prices for construction of <u>1st Street Water Main Replacement From Liberty St</u> to Chestnut St in accordance with the Contract Documents.

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTIT Y	UNIT PRICE	TOTAL
1	WATER MAIN, TRENCHED, PVC DR 18, 6-INCH – CITY WILL PROCURE PIPE	LF	2,210	\$	\$
2	WATER MAIN WITH 18" STEEL CASING PIPE, TRENCHLESS, PVC, 6" – THE CITY WILL PROCURE PVC AND STEEL PIPE, CASING SPACERS, CASING END SEALS	LF	70	\$	\$
3	WATER MAIN FITTINGS, BEND, 6" DI MJ, 90 DEG – THE CITY WILL PROCURE 90 DEGREE BENDS	EA	3	\$	\$
4	WATER MAIN FITTINGS, REDUCER, 6" X 4" – THE CITY WILL PROCURE REDUCER	EA	1	\$	\$
5	WATER SERVICE STUB – THE CITY WILL PROCURE SERVICE LINES OF A LENGTH NEEDED TO REACH THE STOP BOX, TO BE FIELD VERIFIED	EA	26	\$	\$

HR Green, Inc. Project No. 10110158

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTIT Y	UNIT PRICE	TOTAL
6	WATER MAIN ABANDONMENT, CAP, 4" – THE CITY WILL PROCURE CAP	EA	1	\$	\$
7	WATER MAIN ABANDONMENT, CAP, 8" – THE CITY WILL PROCURE CAP	EA	1	\$	\$
8	WATER MAIN ABANDONMENT, FILL AND PLUG, 4" – THE CITY WILL PROCURE PLUGS	LF	2,198	\$	\$
9	GATE VALVE, 6" DI MJ – THE CITY WILL PROCURE VALVES	EA	2	\$	\$
10	INSERTION VALVE, 8" – THE CITY WILL PROCURE INSERTION VALVE	EA	1	\$	\$
11	INSERTION VALVE, 4" – THE CITY WILL PROCURE INSERTION VALVE	EA	1	\$	\$
12	TAPPING VALVE ASSEMBLY, 8"X6" – THE CITY WILL PROCURE TAPPING VALVE ASSEMBLY	EA	1	\$	\$
13	TAPPING VALVE ASSEMBLY, 4"X4" – THE CITY WILL PROCURE TAPPING VALVE ASSEMBLY	EA	1	\$	\$
14	FIRE HYDRANT ASSEMBLY – THE CITY WILL PROCURE HYDRANT ASSEMBLIES	EA	7	\$	\$
15	FIRE HYDRANT ASSEMBLY REMOVAL	EA	3	\$	\$
16	VALVE REMOVAL	EA	2	\$	\$
17	SEAL COAT ROAD RESTORATION	SY	2,507	\$	\$
18	TEMPORARY TRAFFIC CONTROL	LS	1	\$	\$
19	CONSTRUCTION SURVEY	LS	1	\$	\$
20	MOBILIZATION	LS	1	\$	\$
<mark>21</mark>	6" GRANULAR SURFACING	TONS	<mark>790</mark>	<mark>\$</mark>	<mark>\$</mark>

	IR Green, Inc. Project No. 10110158					in Replacement St to Chestnut St Wilton, Iowa
	ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTIT Y	UNIT PRICE	TOTAL
	TOTAL ITEM 1 THROUGH 21					\$
4.	Name of person who inspected site of proposed WORK for your firm:					
		Name:	Da	te of Inspectio	on:	

5. Bidder has examined copies of all the Contract Documents including the following addenda (receipt of all of which is hereby acknowledged):

Number	 Date	

- 6. Failure to acknowledge addenda may render the Bid non-responsive and be cause for its rejection. Bidder has familiarized itself with the nature and extent of the Contract Documents, WORK, site, locality where the WORK is to be performed, the legal requirements (federal, state and local laws, ordinances, rules and regulations), and the conditions affecting cost, progress or performance of the WORK and has made such independent investigations as Bidder deems necessary.
- 7. The Bidder hereby agrees to comply with the additional requirements listed below which are included in this proposal and identified as Bid Form attachments:

ITEM NO. **DESCRIPTION OF ATTACHMENT**

- 1. Bidder Status Form and Worksheet: Authorization to Transact Business
- Section 00430 Bid Bond (Submitted in Separate Sealed 2. Envelope)

To all the foregoing, and including all Bid Forms contained in this Bid, said Bidder further agrees to complete the WORK required under the Contract Documents within the Contract Time stipulated in said Contract Documents, and to accept in full payment therefore the Contract Price based on the Total Bid Price(s) named in the aforementioned Bid Form.

Signed this ______ day of ______ , 2023.

(Firm Name) By:

(Signature)

BID FORM – ADDENDUM 1

HR Green, Inc. Project No. 10110158 1st Street Water Main Replacement From Liberty St to Chestnut St Wilton, Iowa

		(Typed o	or Printed Name)
	-		(Title)
BIDDE	R's name and address:		
BIDDE	R's telephone numbers,	and e-mail address:	
		laura Qa	
Federa	I Tax I.D. No.: (I	Iowa Co DO NOT OMIT)	ntractor License No.:
BIDDE	R's authorized agent for	,	
			Name and Title
BIDDE	R's attesting agent for c	ontract execution:	Name and Title
BIDDE	R's type of business:		artnership, individual, et

END OF SECTION 00400

BID FORM – ADDENDUM 1

	REFER TO THE	SUDAS STANDARD	ESTIMATE REFERENCE INFORMATION SPECIFICATIONS (2021 EDITION) FOR INFORMATION ON THE FOLLOWING BID ITEMS. COMPLETE ALL WORK AS SHOWN ON THE PLANS. IN
		THE	CASE WHERE THERE IS NO BID ITEM FOR THE WORK, CONSIDER THE WORK INCIDENTAL TO OTHER BID ITEMS.
	ITEM NO.	ITEM CODE	DESCRIPTION
8	1	5010-A-1	WATER MAIN, TRENCHED, PVC DR 18, PUSH-ON JOINT, 6-INCH
75	r L		A. BACKFILL MATERIAL MAY BE MATERIAL EXCAVATED FROM THE TRENCH AS LONG AS SUDAS SUITABLE BACKFILL REQUIREMENTS ARE MET. CONTRACTOR IS RESPONSIBLE FOR THE TRENCH COMPACTION TESTING PER SUDAS 3010. 12" STORM SEWER IS INCIDENTAL. CONTRACTOR IS REQUIRED TO FIELD VERIFY EXISTING PIPE TYPE PRIOR TO ORDERING MATERIALS AND CONSTRUCTION FOR THIS WORK. CONTRACTOR IS RESPONSIBLE FOR STORM SEWER PIPE.
	2	5010-B-2	WATER MAIN WITH 18" STEEL CASING PIPE, TRENCHLESS, PVC, 6"
			A. SUDAS SECTION 3020 FOR TRENCHLESS CONSTRUCTION SHALL BE FOLLOWED.
			B. THIS ITEM SHALL INCLUDE BUT IS NOT LIMITED TO THE FOLLOWING: RESTRAINED JOINT C900 PVC CARRIER PIPE, 18" STEEL CASING PIPE WITH MINIMUM WALL THICKNESS OF 3/8", CASING SPACERS WITH A MAXIMUM OF 6' SPACING, CASING END SEAL AND TRENCHLESS INSTALLATION.
	3	5010-C-1	WATER MAIN FITTINGS, BEND, 6" DI MJ, 90 DEG
			A. RESTRAINED ALL FITTINGS USING DUCTILE IRON RETAINING GLANDS; MEGALUG SERIES 110 OR 2000 PV, STARGRIP SERIES 3000 OR 4000 OR APPROVED EQUIVALENT.
			B. ALL DUCTILE IRON FITTINGS SHALL BE WRAPPED IN POLYETHYLENE ENCASEMENT. POLY-WRAP SHALL BE CONSIDERED INCIDENTAL.
	~~~~~~	~~5010-6-1~~	WATER MAIN FITTINGS, REDUCER, 6"X4"
75	5	5010-D	WATER SERVICE STUB
{			A. SERVICE SIZE AND LENGTH TO BE FIELD VERIFIED. DIFFERENT SERVICE SIZES WILL NOT BE COUNTED SEPARATELY. MATCH THE EXISTING DIAMETER ON ALL SERVICE PIPES WITH THE NEW SERVICE LINE. THIS ITEM SHALL INCLUDE ANY AND ALL MATERIALS AND WORK TO CONNECT TO THE EXISTING SERVICE LINE. USE TYPE K COPPER PIPE. CITY WILL PROCURE SERVICE LINES.
	6	5010-F	WATER MAIN ABANDONMENT, CAP, 4"
	7	5010-F	WATER MAIN ABANDONMENT, CAP, 8"
	8	5010-G	WATER MAIN ABANDONMENT, FILL AND PLUG, 4"
			A. EXISTING 4" MAIN SHALL REMAIN ACTIVE THROUGHOUT NEW WATER MAIN INSTALLATION
	9	5020-A	GATE VALVE, 6" DI MJ
			A. PROVIDE VALVE BOX ADAPTOR ii FOR ALL BURIED VALVES.
			B. RESTRAIN ALL VALVES USING DUCTILE IRON RETAINING GLANDS, SEE WATER MAIN FITTINGS ITEM ABOVE.
	10	5020-A	INSERTION VALVE 8"
	11	5020-A	INSERTION VALVE 4"
			A. MANUFACTURER TO BE QUIKVALVE BY ROMAC OR EQUAL
	12	5020-B	TAPPING VALVE ASSEMBLY, 8"X6"
	13	5020-B	TAPPING VALVE ASSEMBLY, 4"X4"
	14	5020-C	FIRE HYDRANT ASSEMBLY
			A. HYDRANT ASSEMBLY SHALL BE FULLY RESTRAINED USING ANCHOR TEE AND PIPE AS IDENTIFIED IN SUDAS FIGURE 5020.201 (WM-201) OR WITH MJ FITTINGS AND DUCTILE IRON RETAINING GLANDS, SEE WATER MAIN FITTINGS ABOVE. HYDRANT TEE IS INCLUDED AS PART OF HYDRANT ASSEMBLY BID ITEM.
			B. FIRE HYDRANT SHALL BE PROVIDED WITH 5-1/4" MAIN VALVE, (1) 4-1/2" PUMPER NOZZLE, AND (2) 2-1/2" HOSE NOZZLES. PROVIDE NATIONAL STANDARD NOZZLE THREADS.
			C. AUXILIARY VALVE SHALL MEET REQUIREMENTS FOR GATE VALVE, SEE REQUIREMENTS ABOVE.
			D. PROVIDE GRAVEL PACK, TRACE WIRE AND F TRACER WIRE TERMINAL POST. INCLUDE ANCILLARY COMPONENTS TO PROVIDE A COMPLETE FIRE HYDRANT ASSEMBLY. E. HYDRANT SHALL BE WATEROUS PACER, CLOW MEDALLION, EJ WATERMASTER, AND KENNEDY GUARDIAN.
	15	5020-J	FIRE HYDRANT ASSEMBLY REMOVAL
	1.5	JUZUZJ	A. SALVAGE FIRE HYDRANT TO OWNER.
	16	5020-K	VALVE REMOVAL
	10	<u></u> συ∠υ⁻Ν	A. REMOVE VALVE BOXES ON ABANDONED WATER MAIN AFTER NEW WATER MAIN HAS BEEN PUT IN SERVICE.
	17	7060-A	SEAL COAT ROAD RESTORATION
	17	8030-A	TEMPORARY TRAFFIC CONTROL
	10	0030-A	A. SUBMIT STREET/LANE CLOSURE TO OWNER FOR REVIEW AND APPROVAL A MINIMUM OF 48 HOURS PRIOR TO CLOSURE.

	19	11010-A-0	CONSTRUCTION SURVEY
			A. ITEM INCLUDES ALL SURVEY AND STAKING WORK AS NECES: CONTRACT DOCUMENTS.
			B. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING FOLLOWING COMPLETION OF THE CONSTRUCTION ACTIVITIES.
			C. ANY PROPERTY PINS DISTURBED BY THE CONTRACTOR SHALL D. CONTRACTOR SHALL SUPPLY OWNER WITH TWO (2) HARD CO
	20	11020-A-0	MOBILIZATION
			A. SEE SUDAS SECTION 11020 FOR PROGRESS PAYMENTS FOR
~	~~~~~	~~~~~~	B. AT LEAST ONE (1) WEEK PRIOR TO CONSTRUCTION ACTIVITI SHALL-CONTACT-OWNER TO OBTAIN APPLICABLE CITY PERMITS.
	21	7030-108-H-3	GRANULAR SURFACING 6"
			A. TO BE PLACED PRIOR TO SEAL COAT PER SUDAS 7030-108-H- ONLY. SALVAGED ROCK FROM EXISTING ROAD SURFACES MAY B
		·····	
		•	*

			ESTIMATED QUANTITIES
	ITEM NO.	ITEM CODE	ITEM DESCRIPTION
	1	5010-A-1	WATER MAIN, TRENCHED, PVC DR 18, 6-INCH
	2	5010-B-2	WATER MAIN WITH 18" STEEL CASING PIPE, TRENCHLESS, PVC, 6"
	3	5010-C-1	WATER MAIN FITTINGS, BEND, 6" DI MJ, 90 DEG
$\sim$	~~4~~	~5010-C-1	WATER MAIN FITTINGS, REDUCER, 6"X4"
2	5	5010-D	WATER SERVICE STUB
$\mathcal{L}$	$\sim \sim \sim$	~~5010-F~~~	WATER MAIN ABANDONMENT, CAP, 4"
	7	5010-F	WATER MAIN ABANDONMENT, CAP, 8"
	8	5010-G	WATER MAIN ABANDONMENT, FILL AND PLUG, 4"
	9	5020-A	GATE VALVE, 6" DI MJ
	10	5020-A	INSERTION VALVE, 8"
	11	5020-A	INSERTION VALVE, 4"
	12	5020-B	TAPPING VALVE ASSEMBLY, 8"X6"
	13	5020-B	TAPPING VALVE ASSEMBLY, 4"X4"
	14	5020-C	FIRE HYDRANT ASSEMBLY
	15	5020-J	FIRE HYDRANT ASSEMBLY REMOVAL
	16	5020-K	VALVE REMOVAL
	17	7060-A	SEAL COAT ROAD RESTORATION
	18	8030-A-0	TEMPORARY TRAFFIC CONTROL
	19	11010-A-0	CONSTRUCTION SURVEY
$\sim$	~20~~	11020-A-0	MOBILIZATION
_}	21	7030-108-H-3	GRANULAR SURFACING 6"
$\sim$			

DRAWN BY: APPROVED:	JWJ	JOB	DATE:	2022
APPROVED:	IMC	JOB	NUMBER:	1011015
CAD DATE:	6/12/2023 \\hrgcrnas\	- 3:19:50	PM	
CAD FILE:	\\hrgcrnas\	Data\1	0110158\	1stStreet

JOB DATE:	2022	BAR IS ONE INCH ON OFFICIAL DRAWINGS.
JOB NUMBER:	10110158	0 Martine DRAWINGS.
19:50 PM		IF NOT ONE INCH, ADJUST SCALE ACCORDINGLY.
ata\10110158\	1stStreetWaterMain\	Design\DWGs\G001dwg

NO.

1

DATE	BY	REVISION DESCRIPTION
5/12/23	LV	ADDENDUM 1



1ST STREET WATER MAIN REPLACEMENT FROM LIBERTY ST TO CHESTNUT ST CITY OF WILTON WILTON, IOWA

ifs: bord

SSARY FOR CONSTRUCTION OF THE PROJECT AS INTENDED BY THE

NG ALL HORIZONTAL AND VERTICAL CONTROL WITHIN THE PROJECT LIMITS

LL BE RE-ESTABLISHED BY A LICENSED SURVEYOR. COPIES OF PROJECT RECORD DRAWINGS.

R MOBILIZATION.

TIES WITHIN PUBLIC RIGHT-OF-WAY AND/OR EASEMENTS, CONTRACTOR

H-3. QUANTITY IS FOR NEW ROCK ONLY AND FOR BIDDING PURPOSES BE REUSED BUT IS CONSIDERED INCIDENTAL.

PLAN QUANTITY AS BUILT QUANTITY UNIT LF 2,210 LF 70 EA 3 _EA  $\sqrt{1}$ EA 26 _____ EA^  $\sim \sim \sim \sim$  $\overline{\ }$ EA 1 2,198 LF EA 2 EA 1 EA 1 EA 1 EA 1 EA 7 EA 3 EA 2 2,507 SY LS 1 LS 1 LS  $\sim^1$ TONS 790